BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38923

APPROVED SCHEDULE - B

E/BTP/BBMP/E-PMT/18/2019-20, Date: 16.11.2019

Improvements to roads and drains at Ramachandrapura, Patel Pillegowda layout and surrounding area in ward no 10 (Doddabommasandra) Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of ASWATHNARAYANA ( )		
				In Figures		In Words
1	811.4	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	256.05	207758.97	Rupees Two Hundred Fifty Six and Five Paise Only
2	120.23	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5677.99	682664.74	Rupees Five Thousand Six Hundred Seventy Seven and Ninety Nine Paise Only
3	313.16	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) etc complete as per specifications and directions of engineer in charge of the work	Cum	6058.59	1897308.04	Rupees Six Thousand Fifty Eight and Fifty Nine Paise Only
4	18.79	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	78977.64	1483989.86	Rupees Seventy Eight Thousand Nine Hundred Seventy Seven and Sixty Four Paise Only
5	1903.8	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	398.42	758512.00	Rupees Three Hundred Ninety Eight and Forty Two Paise Only
6	406.8	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete7.5 cms thick etc complete as per specifications and directions of engineer in charge of the work	Sqm	779.03	316909.40	Rupees Seven Hundred Seventy Nine and Three Paise Only
7	2260	Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	m	64.55	145883.00	Rupees Sixty Four and Fifty Five Paise Only
8	22.56	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	6034.11	136129.52	Rupees Six Thousand Thirty Four and Eleven Paise Only
9	286.2	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge	Sqm	2453.62	702226.04	Rupees Two Thousand Four Hundred Fifty Three and Sixty Two Paise Only

Signature of the contractor

16/03

Executive Engineer

16/03

	pproved Qty.	Description	Unit	Approved Tender Rates of ASWATHNARAYANA ( )		
				In Figures		In Words
10	40.5	Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge	Sqm	5688.36	230378.58	Rupees Five Thousand Six Hundred Eighty Eight and Thirty Six Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/03

16/03